

ENGINEERING 3D DRAWING & ASSEMBLY PLAN

KWIKSTAGE MODULAR SCAFFOLDING STAGE & ACCESS RAMP DRAWING SHEET

ISSUED FOR CREW: 06 OCT 2026 17:24

CAD VERIFIED • STATUS: SOLVED

SITE / EVENT:

Test Stage

CLIENT / PRODUCER:

Festival Co

LOCATION / VENUE:

Arena A

PRIMARY CAD VIEWPORT: [3D ISOMETRIC CAD PERSPECTIVE]

SCALE: N.T.S. (MODEL DIMENSIONS 1:1 METRIC)

GENERAL ARRANGEMENT SPECS

FOOTPRINT DIMENSIONS

4.8m W × 4.8m D

Total Deck Surface Area: 23.0 m²

DATUM WORKING HEIGHT

2.00m (Surface Level)

GROUND SUPPORT STANDARDS

25 Legs

All seated on soleboard footings

DECK ROSTRUM PANELS

8 Full (2.4m) / 0 Half (1.2m)

HORIZONTAL LEDGERS

15 units

Kwikstage 1.2m / 2.4m wedge locking

DIAGONAL SWAY BRACING

16 bays clamped

ACCESS RAMPS & LANDINGS

0 ramps / 0 landings

PERIMETER GUARDRAILS

8 segments

Dual rail (+1.0m / +0.5m)

DRAWING NUMBER:

DWG-TESTSTA-3D-01

APPROVED FOR SITE CONSTRUCTION

REV: A • CAD VERIFIED • PROJECTION: METRIC

SHEET: 01 OF 02

CRUCIAL RIGGING & SITE ERECTION CHECKPOINTS

MANDATORY ENGINEERING SAFETY VERIFICATION & RIGGING CREW HANDOVER CHECKLIST

SITE VERIFICATION: TEST STAGE
SAFETY AUDIT CHECKLIST • SHEET 02 OF 02

Ref #	Category	Crucial Inspection Checkpoint	Engineering Specification / Rule	Permissible Tolerance	Crew Verification	Sign-Off
CP-01	Foundation & Datum	Timber Soleboard Placement & Basejack Seating	300×300×38mm timber soleboards under all basejack footings. Ground compacted and leveled.	Soleboard centered within ±20mm of screw jack plate. Zero soil void under timber.	[] PASS	Initial / Date
CP-02	Foundation & Datum	Basejack Safe Screw Extension Range	Collar adjustment between 150mm and 450mm. Absolute maximum allowable extension 500mm.	Safe zone: 150mm – 450mm. Minimum 100mm thread remaining inside lower standard socket.	[] PASS	Initial / Date
CP-03	Standards & Uprights	Standard Axial Plumbness & Spigot Seating	Standards plumb vertically. Spigot pins fully seated into lower sockets without gap.	Plumb within 1:500 (max ±5mm deviation per 2.0m lift). Zero unpinned spigots.	[] PASS	Initial / Date
CP-04	Horizontal Ledgers	Ledger Ring Seating & Wedge Pin Lock	All ledgers seated into standard star pressings at 500mm intervals. Wedge pins driven home.	Pins driven firmly with 500g hammer until solid ring contact is achieved.	[] PASS	Initial / Date
CP-05	Bracing & Stability	Diagonal Face & Depth Sway Bracing	Diagonal braces installed on perimeter and interior bay lines. Swivel couplers torqued.	Couplers torqued to 50 N·m (37 lbf·ft). Minimum 1 brace per 3 consecutive bays.	[] PASS	Initial / Date
CP-06	Deck Surface	Rostrum Panel Flush Seating & Cam Locks	2.4m×1.2m and 1.2m×1.2m rostrums seated flush in ledger rebates. Under-deck locking bars engaged.	Surface level across adjacent deck joints within ±2mm. Zero lip or trip hazards.	[] PASS	Initial / Date
CP-07	Access Ramps & Landings	Ramp Incline Angle & Landing Transitions	Access ramp gradient conforms to safety guidelines. Intermediate landing pads level (0° slope).	Slope verified "d 1:12 (or industrial). Transition plates flush with ground grade (step "d 6 mm).	[] PASS	Initial / Date
CP-08	Safety & Guardrails	Perimeter Guardrails & Continuous D-Loops	Top rail locked at +1.0m, mid rail at +0.5m. Exposed ends fitted with continuous D-loop returns.	Rail heights: Top 1000mm (±25mm), Mid 500mm (±25mm). Uprights securely pinned to rosettes.	[] PASS	Initial / Date
CP-09	Inspection & Handover	Structural Load Rating & Lead Rigging Sign-Off	Uniform Distributed Load (UDL) rated for 5.0 kN/m² (7.5 kN/m² heavy duty). Physical shake test.	Zero axial slip or joint deflection under test load. Signed handover certificate.	[] PASS	Initial / Date

RIGGING LEAD & SITE SAFETY HANDOVER CERTIFICATE

By signing below, the Lead Rigging Foreman verifies that all listed checkpoints have been physically inspected on-site, and the structure conforms to Kwikstage standards.

Lead Rigging Foreman Signature

Production / Site Manager Approval

Date & Time of Handover